

SECTION 608

SIDEWALKS

608-3.03 SIDEWALK RAMPS. Replace the heading and first sentence with the following:

608-3.03 CURB RAMPS. Construct curb ramps according to the details and the locations shown on the Plans.

608-4.01 METHOD OF MEASUREMENT. Delete Sidewalk Ramp in its entirety and substitute the following:

Curb Ramp. By each installation, complete in place, including ramp runs, flares, and landings necessary to provide a single street-level access.

608-5.01 BASIS OF PAYMENT. Replace Item 608(6) Sidewalk Ramp, with 608(6) Curb Ramp.