

**SECTION 641
EROSION, SEDIMENT, AND POLLUTION CONTROL**

641-3.03 SWPPP INSPECTIONS, AMENDMENTS, REPORTS, AND LOGS.

DELETE subparagraph 3.03.5. Stabilization before Seasonal Thaw and REPLACE with the following:

5. Stabilization before Fall Freeze up and Spring Thaw.

Construction Activities within the Project Zone must be stabilized with appropriate BMPs prior to the anticipated date of fall freeze up, in accordance with the CGP, Section 4.12.

Exceptions to stabilization prior to anticipated date of fall freeze up include:

- a. When stabilization activities are precluded by snow cover or frozen ground conditions prior to the anticipated date of fall freeze up, or
- b. When winter construction activity is authorized by the Engineer and conducted according to the contract.

Construction Activities within the Project Zone must be stabilized with appropriate BMPs prior to spring thaw, as defined in the CGP.