

CR6081. Use CR6081 where work includes either HMA pathways, medians or both. Include only the item included in the project: "Construct HMA pathways;" "Construct HMA medians;" or "Construct HMA pathways and medians."

If there are no sidewalks or curb ramps replace the first sentence as in, "Replace the first sentence with the following" instead of "Add the following."

CR6082. Use CR6082 for exposed aggregate concrete, colored concrete, painted HMA, pattern imprinted concrete and HMA. CR6082 and CR6082 combined with CR6081 and E61 are included in the ALLSPECIALS folder available to be added to the project specials.

608-1.01 DESCRIPTION. Add the following:

Construct asphalt (HMA) pathways and medians.

608-2.01 MATERIALS. Delete paragraph number 2 and substitute the following:

- 2. Asphalt (HMA)
 - Asphalt Binder, PG 52-28 Subsection 702-2.01
 - Aggregate, Type II or III Subsection 703-2.04
 - Mix Design Requirements (ATM 417)
 - Marshall Stability, pounds, min. 1000
 - Percent Voids, Total Mix 2-5
 - Compaction, Blows/side 50

608-3.03 CURB RAMPS. Add the following:

Use a 24" electronic level to measure slopes for curb ramps. Calibrate the electronic level per the manufacturer's instructions.

Add the following Subsection 608-3.05:

608-3.05 ASPHALT PATHWAYS AND MEDIANS. Construct pathways and medians according to Subsection 608-3.02, Asphalt Sidewalks.

608-4.01 METHOD OF MEASUREMENT. Add the following:

Asphalt Pathways, and Medians are measured by the ton of HMA.

Additional HMA used for matching existing surfaces, such as paved parking lots behind a new sidewalk/pathway, will be included in the measurement of the related asphalt Pay Item.

608-5.01 BASIS OF PAYMENT. Add the following:

Asphalt binder is subsidiary to related asphalt Pay Items.

Embankment and bed course materials will be furnished, placed, and paid under Sections 203 and 301, respectively.

Add the following Pay Items:

| <u>Pay Item No.</u> | <u>Pay Item</u> | <u>Pay Unit</u> |
|---------------------|-----------------|-----------------|
| 608(7) | Asphalt Pathway | Ton |
| 608(8) | Asphalt Medians | Ton |