

Whittier Ferry Terminal

Owner: State of Alaska

Terminal Manager: Stephanie Carlson, 907-472-2378

Terminal Description: Whittier is a stern-loading facility consisting of a transfer bridge, twin lift tower syncrolift, 10 steel pile dolphins and associated catwalks/gangways for line-handling access. The facility was upgraded from a timber tidal ramp to a lift and transfer bridge with steel mooring structures in 1988. Modifications were made in 2005 to accommodate the M/V AURORA, M/V KENNICOTT and the Fast Vehicle Ferry, MV CHENEGA. A single-lane highway tunnel and the Alaska Railroad provide access to Whittier from Anchorage and Portage. Like Valdez, this is a key connection point between Cordova and Anchorage. Tourism accounts for much of the summer traffic volume through this port. The facility went to year round service starting in 2005 with the reopening of the new modification project. The past 10 years of total passenger and vehicle traffic at Whittier is shown below.



The most recent above water survey & fracture critical inspections were completed on August 12, 2018. The underwater survey occurred on August 3, 2018.

Vessels						
Name Berthing, Alignment						
Aurora/Kennicott/FVF	Stern					
Tidal Data (MLLW 0.0 feet)						
EHW	18.7					
MHHW 12.3						
MHW 11.3						

Terminal Building			
Year Built:	2005		
Square Footage:	2200 s.f.		
Heating System:	Furnace (Natural Gas)		
Fuel Storage:	City Supply (Natural Gas)		
Fire Protection:	Alarm Pyrotronics		
Condition:	New		

-6.0

ELW

Generator & Building			
Building/Generator:	2005		
Square Footage:	260 s.f.		
Heating System:	Electric		
Fuel Storage:	City Supply (Natural Gas)		
Fire Protection:	Halon		
Condition:	Good		

Uplands				
Short-Term Parking: 3 cars				
Long-Term Parking:	N/A			
Staging Area: 1200 lineal feet; 125				
	lineal feet-buses/trucks			
Paint Striping:	Yes			
Driving Surface:	Asphalt			

Vehicle Transfer Bridge - #1424			
Туре:	16' x 140' twin box beam		
Year Built:	1986		
Shoreward support:	Concrete abutment		
Seaward support:	Steel Lift Beam-Syncrolift		
Coating:	Wasser Paint		
Pedestrian Access:	Concrete 4' wide on bridge		
Lighting:	None		
Condition:	Good (see findings)		
Load Posting Sign:	N/A		
Original Design Load:	HS 20-44		

	Utilities	
	at Terminal	at Ramp
Electrical:	Yes, city & back	up power
Water:	Yes	No
Sewer:	Yes (Septic)	No
Telephone:	Yes	Yes
Cable TV:	No	No
Fuel:	No	No
Wireless Bridge:	Yes	_

	Dolphins							
Dolphin	Dolphin Piles	Fender Support	Fender Face	Anodes	Built	Cond.	Hawse Extensions	Notes
N3	3B, 3V	Hanging	UHMW	Yes	2005	New	Yes	Red navlight
N2	1B, 1V	Floating	Rubber Fender	Yes	2005	New	Yes	
N1	2B,2V	Hanging	UHMW	Yes	2005	New	Yes	
ST	4V	-	-	Yes	1988	Good	-	
NT	4V	-	-	Yes	1988	Good	-	Light Pole
S1	2B,2V	Hanging	UHMW	Yes	2005	New	Yes	
S2	1B,1V	Floating	Rubber Fender	Yes	2005	New	Yes	
S3	2B,2V	Hanging	UHMW	Yes	2005	New	Yes	
S4	2B,2V	Hanging	UHMW	Yes	2005	New	Yes	
S5	2B,2V	Hanging	UHMW	Yes	2005	New	Yes	Light Pole
S6	2B,2V	Hanging	UHMW	Yes	2005	New	Yes	
S7	3B, 3V	Hanging	UHMW	Yes	2005	New	Yes	Red navlight & windsock

	Catwalks / Gangways							
#	From Struc.	To Struc.	Length / Style / Main Members	Built	Safety Chains?	Cond.	Lighting	Notes
C1	N3	NT	34' / Catwalk / W 12x26 Custom Girders	2005	No	Good	Tubuloid	
C2	NT	N1	9' / Catwalk / W 4x13 Bottom Chord	1988	No	Good	Tubuloid	
Gl	ET	EBP	52' / Gangway / S 4x9.5 Bottom Chord	1988	Yes	Good	Tubuloid	
G2	WT	WBP	52' / Gangway / S 4x9.5 Bottom Chord	1988	Yes	Good	Tubuloid	
C3	ST	S1	9' / Catwalk / W 4x13 Bottom Chord	1988	No	Good	Tubuloid	
C4	S3	ST	33' / Catwalk / W 12x26 Custom Girders	2005	No	Good	Tubuloid	
C5	S4	S3	57' / Catwalk / W 18x40 Custom Girders	1988	Yes	Good	Tubuloid	
C6	S5	S4	65' / Catwalk / W 18x40 Custom Girders	2005	Yes	Good	Tubuloid	
C7	S 6	S5	72' / Catwalk / W 18x40 Custom Girders	2005	Yes	Good	Tubuloid	
C8	S 7	S6	61' / Catwalk / W 18x40 Custom Girders	1988	Yes	Good	Tubuloid	

LEGEND

 $\overline{\text{ET} = \text{East}}$ Lift Tower G1 = Gangway V = Vertical Steel Pipe Piling EBP = East Bridge Platform B = Battered Steel Pipe Piling

	Terminal Projects					
Year	Project #	Project Name	Description			
1988	RS0830(1)	Whittier Ferry Terminal	Expanded uplands staging and parking area and constructed generator building. Dredged the mooring basin. Removed existing transfer structures and replaced with new steel transfer bridge and Syncrolift system. Removed existing timber mooring structures and replaced with steel mooring/fendering structures connected with steel access catwalks. Lighting and hydraulic lift control upgrades.			
2005	67883 / NH- 0496(007)	Whittier FT Improvements - Uplands & Terminal Building	Constructed uplands improvemnets, built new terminal and generator buildings and made utility upgrades.			
2005	68335 / NH- 0830(2)	Whittier FT Terminal Modifications	Removed existing mooring structures and replaced with ten new steel mooring/fendering structures.			

	Terminal Projects (cont'd.)					
Year	Project #	Project Name	Description			
2008	73741	WIT Ferry Terminal Transfer Bridge Repairs	Harbor Welding repaired the FB-Girder weld cracks Dec 4th - 18th, 2008.			
2008	69050 / SHAK - 0005(575)	Whittier - Ferry Dock Hoist Upgrade	Replaced the existing relay-based control panel for the transfer bridge lift system with a PLC-based control panel.			
2011	N/A	WIT FT Building Repairs	Remove clerestory window & water-damaged wall frame.			
2013	73125 (1)	WIT Staging Area Lighting Replacement	Remove & replace all exterior light fixtures in the staging area; replace conduit/wiring below the bridge, relocate to above the girder; other miscellaneous electrical			
2013	N/A	Emergency Hoist Repairs	Repairs consisted of the complete replacement of all lift system components.			
2016	N/A	WIT FT Bridge Strengthening	Installed a structural retrofit to the seaward end of the bridge to bring the load rating within standards for highway vehicles.			

Observations

- 1. A repair project for the terminal building was designed & constructed in 2011.
- 2. Land area in Whittier is constrained. The ferry terminal property is substandard in size for the parking & staging needs of the Whittier terminal. Public parking near the terminal building may be insufficient. The staging area should be bigger to accommodate current & future traffic. The bridge transition plate is wearing into the pavement at the shore approach. There is a damaged section of guardrail near the bridge abutment. There are long pavement cracks near the transfer bridge abutment.
- 3. A project in 2013 replaced all the light poles with new high-wind rated poles.
- 4. The bridge is supported on the seaward end by a Syncrolift cable support system. The shore side end is supported by hinge bearings on a concrete abutment. In 2007, a frozen "normal up" limit switch on the left hoist of the Syncrolift led to one of the bridge girders being raised 4-feet higher than the other. Terminal personnel determined the cause of the problem, cleared the ice from the switch, and then the bridge operated normally. The problem has not reoccurred. Follow-up inspection revealed failed welded connections between the first floor beam and both girders. AMHS Shoreside Maintenance contracted the repair out to a certified-welder, Harbor Welding, and repairs were completed in December of 2008. On-site QC, including various methods of NDT, was performed by Mayes Testing Engineers.

On the following inspection cycle in 2010, rust staining was discovered along the bottom of the first floor beam-to-girder connections. QA Services, out of Anchorage, removed the paint and verified the extents of the weld cracks with NDT methods. The most recent inspection found the following weld cracks:

Girder 2 (RT) - FB 0 Exterior:

- 1-1/2" crack between the top flange of FB and the Girder web.
- A crack wraps around the top shoreward corner that is 1-1/2" along the top flange and 6-1/2" along the shoreward web of the FB.

Girder 1 (LT) - FB 0 Exterior:

- 1-1/8" long crack between the top flange of FB and the girder web.
- A crack wraps around the top shoreward corner that is 7-1/2" along the top flange and 4" along the shoreward web.
- There is a 3-3/4" long crack between the girder end plate and girder web
- A crack along the entire lower flange of the FB and wraps around both corners and up the web of the FB on both sides 3"

Girder 2 (RT) - FB 0 Interior:

• 1-3/4" crack reflecting through the web from the exterior, near the first bearing stiffener

Observations (continued)

• 5" crack reflecting through the web from the exterior, near the girder end plate

Girder 1 (LT) – FB 0 Interior:

- 3" crack reflecting through the web from the exterior, near the first bearing stiffener
- 4" crack reflecting through the web from the exterior, near the girder end plate

These weld cracks have continued to propagate, albeit at a slow annual rate, along the web weld between the FB and Girder. This weld is the primary path for load transfer of vehicle loads.

5. The 2006 inspection of the transfer bridge discovered that the pin of the right shoreside hinge is rotating relative to the base. The keeper bars, that restrict movement of the outboard nut, have been forced aside, permitting the nut to rotate as the bridge is raised and lowered. Shore personnel have been alerted to monitor the position of the pin. The most recent inspection found the gap between the nut and the bearing assembly hasn't changed in several years.

The seaward hinge bearings, on the lift beam, do not appear to rotate as the bridge is raised or lowered. Most likely the bearing surfaces seized due to inadequate lubricating grease. The platform on the lift beam for maintenance access is too narrow to use, so greasing can only be done from skiff.

- 6. An AMHS Maintenance project replaced the 2005 PLC controls with a new PLC automated control system in 2008. The bridge controls have stabilized, but if faults occur, they can be monitored on the internet. The elevation of both girders is gauged, and the software was written to stop operations and reset levels when an elevation variation greater than 2" occurs.
- 7. Heavy condensation exists on the interior of girder 1 and 2 and all associated components. These moist conditions have resulted in heavy laminating corrosion on top of the bottom flange plate, with up to 1/16-inch section loss. Several custom clamps holding down the open grid deck are loose or unfastened. When the apron is stowed in the 'up' position, during heavy offshore winds it can be blown shoreward and locked in place. The only method of freeing up the apron is to lower the bridge, which drops the apron suddenly onto the apron lift beam. Water enters the box girders thru open vent caps on the seaward ends, gaps in the access hatch doors & the multiple cracks at the shoreward ends
- 8. The Whittier facility is unique in that the apron rotates to a vertical, down position for use by the MV Aurora. The bridge apron is lowered out of the way to permit the Aurora to place its stern apron directly on the bridge. In the down position (only when the Aurora is in port), approximately half of the apron is submerged and the apron is subjected to wave forces. Wave motion causes the apron to pound against the stops and purportedly deflects the lift arm support some 4 inches in severe weather.

Typically the bridge is lifted all the way up to the tower, in order to reset the syncrolift winches. But if the apron is left in the water, the force of the waves may cause damage to the apron hinges, lift arm, or its supports. The simple solution is to keep the apron out of the ocean environment as much as possible. Perforating the apron will reduce the induced wave forces. In addition, the apron may be braced by supports at a lower elevation to reduce the loads resisted by the arm support.

- 9. In August, 2013 an electrical contractor was employed to relocate conduits and conductors from under the bridge to the top flange of both box girders. A level bench of riprap extends several feet in front of the abutment creating a shelf for snow to accumulate under the bridge. Electrical conduits suspended from the floor framing are repeatedly crushed against the snow mound when lowering the bridge at low tides. This work remedied the problem by moving the conduits to the top of the box girders where they are no longer at risk for damage. When replacing the conductors the electrical contractor mistakenly reversed the power feed to the Syncrolift hoist motors. When the hoist was activated after the wiring modifications, the brake pawls did not retract as the bridge was lowered. The winch drum was driven against the pawl, completely failing the winch drum pillow blocks on both hoists. Replacement parts required a 6 month lead time; therefore, the hoists were replaced in their entirety with used units and the terminal was reopened in November, 2013.
- 10. In 2015 a bridge load rating performed by Burgess & Niple, Inc. consulting engineers indicated deficiencies in floor beam 14 and some of the cantilevered stringers at the seaward end of the bridge. An independent rating by ADOT&PF Marine confirmed a component LFR of 0.36 for the floor beam and similarly low values for the stringers. On November, 2015 the Marine Design section conducted a special inspection of the overloaded members but found no indication of distress or excessive deflection.

In May 2016 a bridge strengthening project added two floor beams to the underside of the bridge's seaward floor framing to remedy the deficient floor beam and stringers. The rating factors of all

Observations (continued)

elements at the seaward end increased above 1.0 but the overall bridge rating factor is 0.82, limited by the capacity of floor beam 11. ADOT&PF policy does not require posting of this bridge as the LFR rating exceeds 0.75.

- 11. The tube shaped light fixtures, mounted on bridge, catwalk & dolphin handrails, have failed due to infiltration of rain water. There are several loose connections in the liquid-tight plastic conduit beneath the transfer bridge. Several bridge grating clamps are broken. The 2006 inspection noted that the catwalks still sway/rotate under pedestrian loads, even after the addition of cross bracing. The non-skid coating is cracking along the edges of the dolphin caps, but is in serviceable condition. The stern all-tide mooring floats (single vertical pile and batter pile) sway sideways approximately 1 foot during high wave conditions. This could be minimized by installing a strut to the stern mooring structure batter pile.
- 12. The UHMW face was detached from the fender panel of dolphin N1. Thermal expansion of the plastic causes the panels to expand, and shear off the metal studs. Lower fender panels on dolphin N3 were pried off, bolts were missing and numerous scrapes were observed on the UHMW. AMHS Maintenance repaired both the N1 and N3 fender panels in April of 2013. Depth to mudline elevations, taken with leadline readings at each mooring dolphin along the fender face in 2018, range from -28 to -46 MLLW.
- 13. The steel retaining brackets for the lowest elevation energy-absorbing rubber donuts have failed on dolphin N1. The most recent underwater inspection found all piles exhibit loss of galvanizing within the splash zone, while below low water level the galvanizing is generally intact except for isolated areas of coating damage. Section loss at coating damage is consistently 4-5%, very minor. Most of the cathodic protection consists of stainless steel cables hung from a welded stud on the pile, connected to an aluminum bar anode. Most of the anodes are buried in the seafloor, rendering them ineffective. Seawater potentials measured at each structure ranged from -0.63 to -0.64 V, thus indicating inadequate Cathodic Protection (CP) readings, freely corroding steel.
- 14. The northwest edge of the bridge stringer has a section of damaged coating, with corresponding scrape mark on the batter pile from dolphin N1. Assumption is that the stringer bears on the edge of the batter pile, possibly only during rough weather (when apron is placed on the vessel deck). Another possible cause could be seized hinge bearings on the seaward lift beam. This was first noted on inspection in 2006, one year after the project added a riser between the bridge and lift beam. Investigations of this matter to date are inconclusive.

	Inspection Summary				
Structure	e Priority Recommendations				
		Category I - Safety Repairs			
Transfer Bridge - Shoreward bearings	Transfer Bridge - ShorewardProgram a project to repair the cracks in the connection between Floorbeam 0 and both Girder webs. Analyze what the potential causes of the cracks stem from (seaward end of bridge contacting piles of stern dolphins, bearing on packed snow/ice at abutment, cyclical fatigue from movement at Syncrolift, etc). Remove the stop bars on the south bridge hinge pin, tighten the nut down, re-weld stop bars.				
		Category II - Rehabilitation Work			
Bridge Lifting Beam Access	Bridge Lifting Beam Access 2 Program a project to install an access ladder on the lift tower and a wider platform on the seaward bridge lift beam, similar to the designs in Valdez/Wrangell.				
Bridge Apron 3		Consider replacing the hinges and/or modifying the apron to allow it to be left in 'stowed- down' position, such as installing open-grid decking to pass water through. Build stop wedges so the apron doesn't rotate shoreward when left in 'stowed-up' position during high winds.			
Transfer Bridge4Repair the paint coating to the interior girders, stringers, and bridge curb during the beam weld repair project. Replace broken open-deck grating hold down rods and pla					
Hawse Rails 5 Program a project to cut back the hawse rail extensions and replace them with welde padeves on hawse rail ends and catwalk railing with heavy rope in-between.		Program a project to cut back the hawse rail extensions and replace them with welded padeyes on hawse rail ends and catwalk railing with heavy rope in-between.			

		Inspection Summary (continued)			
Structure	Priority	Recommendations			
Hand Rails	6	Program a project to drill holes at the bottom of vertical chords in the hand rails. Straighten bent handrails where damage is observed when funding is available.			
Dolphins	7	Replace the hanging anodes with welded-on bar anodes. Repair the broken fender mounting bracket on dolphin N1. Remove & replace all damaged stud welds on UHMW facing panels. Monitor donut bracket plates at S5 and N1 dolphins and monitor the deck surface corrosion on dolphin S6.			
Miscellaneous	8	Remove gouged pavement and install a concrete pad beneath the shoreward bridge transition plate. Replace the tubaloid light fixtures with 'jelly jar' fixtures. Install a strut between the all-tide mooring dolphins and the stern mooring dolphins. Install safety cables on catwalks. Repair field-applied weld coatings where they're failing. Install a vent cap on the seaward end of the bridge girders.			
		Category III - Upgrades Needed			
Lift Tower	9	When funding is available, program a project to design/construct a full enclosure for the lift towers (similar to Valdez).			
Structure Removal	10	Schedule to remove a structure in front of the ferry terminal to improve traffic flow and parking.			
Terminal Parking	11	Program a project to increase the parking capacity at the ferry terminal.			